



STREAM NO.	5001	5002	5003	5004	5005	5006	5007 (NOTE 7)	5008
TEMPERATURE, °C	47	25	37	37	37	37	37	60
PRESSURE, Barg	3.5	5.5	5.5	0.31	5.5	5.5	2	4.5
TOTAL MASS FLOW, kg/h	2.5E+07	532430	2.5E+07	2.6E+07	74882	1248029	520	2900
DENSITY, kg/m3	990.7	1007.5	998.4	998.3	998.4	998.4	998.3	983
VISCOSITY, Cp	0.57	0.89	0.69	0.69	0.69	0.69	0.69	0.46

REFERENCE DRAWINGS

DWG. NUMBER

Note :

- DELETED.
- DELETED.
- DELETED.
- DELETED.
- 7 ELECTRICAL PUMPS ARE CONSIDERED FOR COOLING WATER PUMPS. (5 DUTY PUMPS + 2 SPARE PUMPS).
- REQUIRED CONTROL FLOW VALVE SHALL BE CONSIDERED BY FILTRATION PACKAGE VENDOR.
- STREAM PRESSURE AND BACK WASH FLOW RATE ARE PRELIMINARY AND WILL BE FINALIZED BY VENDOR DURING DETAIL DESIGN.
- DELETED.
- DELETED.
- 6 (5+1) COOLING WATER CELLS CONSIDERED.
- DELETED.
- DELETED.
- DELETED.
- DELETED.
15. THE LOCATION OF PACKAGE 83-W-901 WILL BE CHECKED AND FINALIZED DURING DETAILED DESIGN ENGINEERING PHASE AS PER CONTRACT.
- WILL BE FINALIZED LATER

Legend :

01

00

01	ISSUED FOR APPROVAL	22-Sep-2025	A.HOSEINGOO	M.JAMSHIDI	M.H.ESHRAGHI
00	ISSUED FOR COMMENT	18-Dec-2024	M.FALAHI	M.JAMSHIDI	E.SHAFAGHATI
REV.	PURPOSE OF ISSUE	ISSUE DATE	PREPARE	CHECKED	APPROVED
OWNER:			MC:		
PROJECT TITLE:			CONTRACTOR/CONSULTANT:		
PROPANE DEHYDROGENATION (PDH) PROJECT					
DOCUMENT TITLE:					
PFD for Cooling Tower System					
DOC NO.:	PROJ.CODE	Sec.	PHASE	DEP.	DOC. TYPE
	3981	50	DE	PR	PFD
SCALE: 1:100	SIZE: A3	SHEET NO: 1 OF 1		REVISION: 01	CLASS: 1

This document contains confidential proprietary information belonging to Pars Petrochemical Co. and shall not be disclosed to any third party without the prior written consent of Pars Petrochemical Co.